

# Republic of the Philippines Department of Education (DepEd) National Capital Region



# DIVISION OF CITY SCHOOLS QUEZON CITY

Nueva Ecija St., Bago Bantay, Quezon City

September 29, 2011

# FORMING AND ORIENTING THE BAYANIHANG ESKWELA SCHOOL BASED MONITORING TEAMS IN SCHOOLS WITH RED AND BLACK SBPs OR REGULAR SCHOOL BUILDING PROJECTS


#### **MEMORANDUM TO:**

Assistant Schools Division Superintendents Division/District Supervisors Elementary and Secondary School Heads School PTA Presidents Girl/Boy Scout Council Executives

- 1. On its 6<sup>th</sup> year, *Bayanihang Eskwela* has been officially adopted by the Department of Education as its community based monitoring of government school building projects nationwide through the recently adopted DEPED ORDER NO. 21, S. 2011 (DATED MARCH 4, 2011): Guidelines on the Institutionalization of "Bayanihang Eskwela" as a Community-Based Public-Private Monitoring of Projects Under the CY 2011 Regular School Building Program (RSBP) and in Areas Experiencing Acute Classroom Shortage (Red and Black Schools).
- 2. Bayanihang Eskwela is a joint public-private initiative founded on the spirit of "bayanihan" or volunteerism among the Filipino people. It was initially spearheaded by the Ateneo School of Government through its Government Watch Program, in partnership with the Department of Education, the Department of Public Works and Highways (DPWH), the Office of the Ombudsman (OMB), the Girl Scouts of the Philippines and the Boy Scouts of the Philippines, that aims to ensure provision of quality classrooms through community-based monitoring of school building projects (SEE ATTACHMENT A).
- 3. The Bayanihang Eskwela Nationwide Roll-out has been set last August 18, 2011 at the Bulwagan ng Karunungan, Department of Education, Meralco Avernue, Pasig City, with partners which included more civil society organizations: the National Confederation of Parents, Teachers and Community Associations (PTCA's), Civil Society Network for Education Reforms, Public Service Labor Independent Confederation (PSLINK), Procurement Watch Incorporated (PWI), Northern Luzon Coalition for Good Governance (NLCGG), Concerned Citizens of Abra for Good Government, Incorporated (CCAGG), Western Visayas Network of Social Development NGOs (WEVNET), Consortium of Bangsamoro Civil Society, Young Moro Network for Social Accountability, and many more.
- 4. Division Coordinating Groups (DCGs) were also formed through a series of nationwide briefing orientations. DCGs are composed of representatives from identified government and civil society organizations in the different DepED divisions tasked to orient school-based monitoring teams (SBMTs) on how to conduct community based monitoring of school building projects.
- 5. The *Bayanihang Eskwela* Division Coordinating Group (DCG) in the Division of Quezon City are as follows:

- 6. Your school is a beneficiary of a school building project from the Department of Education. Herein, we invite you to form your *Bayanihang Eskwela* School-Based Monitoring Teams (SBMTs) to help in ensuring quality school building construction in your school.
- 7. As per DepED Order 21, s. 2011, The BayEsk SBMTSs are composed of the following:
  - a. School Head/Principal. The school head/principal shall be responsible in inviting the PTA representatives, the School Boy Scout and Girl Scout Coordinator, and local Non-Government Organization.
  - b. PTA Representatives. At least one (1) representative from the PTA shall be a member of the team.
  - c. School Boy Scout and Girl Scout Coordinators. They shall be automatically members of the team with the condition that they shall report to their local councils of the activities of the team.
  - d. Local NGOs. Representatives from local NGOs shall be invited to b part of the team.
  - e. Project Engineer. The project engineer either from DedED (for Red and Black SBP) or from DPWH (for RSBP) depending on the implementing agency, shall automatically serve as the technical expert of the team.
  - f. Division Physical Facilities Coordinator (DPFC). The Division Physical Facilities Coordinator shall be automatically part of the team to represent the Division Office and shall further be the initial coordinator of the team before the election of the School-Based Monitoring Team Coordinator.
- 8. Once you have formed your team, please review and accomplish the easy-to-use Bayanihan Eskwela Checklist (SEE ATTACHEMENT B).
- 9. For further instruction on how to answer it your may contact the Division Physical Facilities Coordinator or the Division Coordinating Group through the contact details given above.
- 10. Your SBMT is expected to pass the accomplished checklist as soon as possible to the DCG.
- 11. The Division Office would also like to invite you to a short orientation with the Division Coordinating Group on how to answer the Bayanihang Eskwela checklist on your most convenient time at the Division Office. The DCG shall also provide you with some monitoring tips to guide you the monitoring your school building project

YOLANDA C. ARCO Chief Administrative Officer Officer In-Charge



## The Bayanihang Eskwela Checklist

The G-Watch Checklist for the monitoring of school building construction projects under the Bayanihang Eskwela is an easy-to-use guide for ordinary, non-technical people. It must be brought during the actual monitoring visits to the project site.

#### Components

It consists of six major components, namely the school profile, pre-construction, construction, and post-construction stages, as well as the conduciveness to learning and responsiveness to school need. Under the stages are key activities and/or and indicators.

#### Format

The checklist has four columns. The first column contains the "Monitoring Points", which are in question-form answerable by "yes" or "no". The monitor simply checks the second or third columns, which are the "Yes" or "No" columns, respectively, to answer the questions. The fourth column asks for "Details" of the answer. Some details are pre-determined in boxes that have to be checked if they have been fulfilled while others

ask for date, place and measure of area or observations and elaboration.

In the "Structure" section of post-construction stage, the first column is also called "Monitoring Points". It contains the features to look for in a completed school building. The second and third columns contain the (+) and (-) signs, respectively. They must be checked accordingly depending on whether the feature is "present" or "absent" based on the requirements of the Program of Works. The fourth column asks for "Comments and Observations".

#### Coordination and Other Tasks

Refer to the Organizational Structure and Field Monitoring Coordination Plan at the back. The monitor must immediately report any problem encountered during the monitoring. The report must be sent to the School Principal, local DPWH. authority, Physical Facilities Coordinator of the DepEd Division or to G-Watch (text 0927-832-3734 or government watch@yahoo.com).

The monitor must also take photos of the construction activity or the structure being constructed during the period of monitoring.

#### POINTERS ON MONITORING

#### What is monitoring?

Monitoring is active involvement in the implementation of a project, which entails:

- watching the implementation with the main objective of the project in mind
- comparing the plan and standards with the actual accomplishments
- checking particular aspects of the project in its various stages
- recommending remedial actions, if necessary

#### Guide monitoring questions:

- At what stage is the project in terms of schedule, budget and required specifications?
- What were accomplished according to the plan and what were the unexpected circumstances?
- What caused problems in the implementation?
- How can the problems be solved? Is it necessary to revise the plan, the schedule or the budget?


#### Things to monitor:

- budget
- schedule
- work procedure


### Don't forget to bring the following:

- G-Watch Checklist
- Copy of the Program of Works
- Notebook and pen

### Organization Structure



## Monitoring Coordination Plan



# (1) chedest. 10ge 2

MONITORING PROFILE						
Name of School:		Name of N	flonitor (s):			
Location: District:				.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
Division:		Organization:				
Project:						
Contractor:						
Planned Duration:		Sex:				
Planned Cost:		Age:				
GENERAL SCHOOL PROFILE						
GENERAL SCHOOL NEEDS (get data for	rom the BEIS) Performance Indicato	irs .				
Student Population		2008:	2009:	2010:		
Male Female  Teacher-student Ratio	National Achievement Test					

Student Population	on		
*Male	ranor-makera aman	Female	
Teacher-student	Ratio		
Textbook-student	Ratio	× 22 × 22 × 22 × 22 × 22 × 22 × 22 × 2	
· Math		Makabayan	
Science			
English			
Filipino			
Classroom-studer	nt Ratio		
Seat-student Rati	0 .		
Blackboard-Class Ratio	sroom		

ASS IN DESCRIPTION OF SELECTION	2008:	2009:	2010:
National Achievement Test			
Participation Rate			
Dropout Rate			
Cohort Survival Rate			

# PRE-CONSTRUCTION STAGE

s No	Details
	Type of Property □ public property □ donated private property □ expropriated private property
	□ geographical concern □ environmental concern □ social concern □ other concerns
	When: Where: Represented offices/groups: DPWH PTCA DepED NGO LGU DENR Barangay Office

			□ LGU □ Barangay Office □ PTCA □ NGO □ DENR
Was the project management team formed?     Binuo na ba ang project management team?			Name of Project Head:
3. Was the documentation of property ownership in order? Maayos ba ang dokumentasyon ng pagmamay-ari ng lupa?			Type of Documentation  Deed of Donation  Sale Document  Annotated Original / Transfer Certificate of Title
Activity 3: Pre-Engineering Survey			
Was a pre-engineering survey conducted?     Nagsagawa ba ng pre-engineering survey?	1		When: Lead in the survey: Observations:
2. Did the survey confirm that the building to be constructed fit the land area?  Nakumpirma ba ng survey na kasya ang itatayong gusali sa napiling lugar?			Area needed: Area available:
Activity 4: Preparation of the Program of Works			
Was the School Principal consulted on the Plans and Program of Works?     Kinunsulta ba ang School Principal sa plano at Program of Works?	ę		
2. Were you given a copy of the Program of Works? Binigyan ka ba ng kopya ng Program of Works?			Cost: Duration:
3. Did you have difficulty getting a copy of the Program of Works?  Nahirapan ka bang himingi ng kopya ng Program of Works?		7	Elaborate:
4. Is the Program of Works consistent with DepED standards? Ang Program of Works ba ay naaayon sa itinakdang pamantayan ng DepED?			DepED standards:  cemented floor smooth finished walls painted walls, ceiling and roofing
			□ full cathedral-type ceiling (for single-storey) or drop ceiling (for multi-storey) □ complete set of windows (2 facing walls)
			□ two entrances with doors □ complete electrical wires and fixtures □ roofing or weather protection □ blackboard
Activity 5: Site Inspection			9
Was a site inspection conducted?  Nagsagawa ba ng site inspection?			When: Where: Represented offices/groups: DPWH PTCA DepED NGO LGU DENR Barangay Office
Did DPWH/DepEd give orientation on project plans during site inspection?     Nagsagawa ba ng project orientation?			When:
3. Was the information given in the orientation consistent with the Program of Works?  Ang impormasyon bang ibinigay sa orientation ay naaayon sa nakasaad sa Program of Works?			Inconsistencies (if any):
Activity 6: Bidding		,	If ves

		If no, Mode of procurement used: Amount of Contract: Name of Contractor:
2. Were there issues and concerns raised?  May mga usapin bang tinalakay?		Elaborate:
3. Was post-qualification conducted?  Nagsagawa ba ng post-qualification?		Lowest Calculated Responsive Bids: 1. 2. 3.
Did you do your own checking of contractor's capacity?  Nagsagawa ka ba ng sariling pagsisiyasat sa kapasidad ng contractor?		Findings:
5. Was the Notice to Award sent to the winning bidder? Naipadala ba ang Notice of Award sa nanalong bidder?		When:
6. Did the winning bidder send Letter of Acceptance?  Nagbigay ba ng Letter of Acceptance ang nanalong bidder?		When:
7. Was the Notice to Proceed sent to the winning bidder? Naipadala ba ang Notice to Proceed sa nanalong bidder?	*	When:

# CONSTRUCTION STAGE

Monitoring Points	Yes	No	Details
Activity 1: Earthworks and Excavation	L		A
1. Were garbage, plants, remains of old structures, and other obstructions removed and disposed of properly?  Maayos bang tinanggal at itinapon ang mga basura, halaman, tira ng lumang istruktura at iba pang sagabal sa konstruksyon?			Observations
2. Were there items (e.g. structures, trees) that had been unnecessarily damaged?  Mayroon bang bagay, istruktura o puno na aksidenteng nasira?		i e en ou	What: Who is responsible for the damage?
3. Was the excavation area in accordance with the plan in the Program of Works?  Ang sukat ba ng excavation ay ayon sa plano sa Program of Works?	-		Planned Area in Program of Works: Actual Excavated Area:
4. Did the excavation disturb any slopes?  May nasira bang talilis dahil sa paghuhukay?			Observations:
5. Was the excavated surface smooth and uniform? Patag at pantay ba ang ibabaw ng hukay?	+		Observations:
6. Were the excavated materials disposed of properly?  Itinapon ba nang maayos ang mga nahukay?			Observations:
7. Were the excess materials (e.g. rocks and boulders) used as backfill materials?  Ginamit bang backfill materials ang mga bato?			If yes, was there permission from the Project Engineer?
Activity 2: Concrete Works			

Nakaimbak ba nang maayos ang mga bag ng semento?	7		I a Paga of an		
and many standards and mad baying sementor			room	ment may get v	vet in the storage
				m has cracks	Or openings
			between wall	s and roofs	or openings
			☐ Flooring is	above ground	
			□ Cement ba	gs are stacked	close together
and the second s					3-1-1
3. Were cements that already solidified or which contain	-	-	Observations Observations	***************************************	
lumps of caked cement still being used?		Sec.	Observations	endqes.	MIR. Y
Ginagamit pa rin ba ang mga sementong namuo-muo at			11111111111111		
nagkatipak-tipak na?					Carly 1
4. Were cements salvaged from discarded or used bags still	-	1	Observations		
being used?			a soor valions.		
Ginagamit pa rin ba ang mga tira-tirang semento?					
5. Did they mix cement with clean water?		1	Indicators:		
Malinis na tubig ba ang hinahalo sa semento?				lat / no acid / n	o álcali / no
			grass	, , , , , ,	
6 Ware quality course aggregates ()			Observations:		
6. Were quality coarse aggregates (gravel) used?			Indicators:	Street Land Control	
Tamang kalidad ba ang ginagamit na graba?	i	I Bills A	Color is blue	, not brown / C	lean, no mixture
			of soil or clay	Hard, strong a	and durable; do
	1 2 2	-	coatings or cry	ly / Free from a	any adherent
	74.		coatings of city	/Stats	
*			Observations:		
7. Were quality fine aggregates (sands) used?			Indicators:		
Tamang kalidad ba ang ginagamit na buhangin?			☐ Must come f	rom the river, r	not sea (color:
			black) / Sands	from different	sources are not
	* * *		combined toge	ether	
			Observations		- Aria
8. Was the correct proportion of water, cement and			Observations:		
aggregates followed in the construction of columns and		no.		20% / Cement	70/ 4/0/ /
beams?	a wuga	12 5 4	Aggregates: 68	3%-78%	. 1 /3-14/01
Sinusunod ba ang tamang panumbasan sa paghahalo ng	Cartes		33.3	270 1 070	Consens
tubig, semento at aggregates?	THE PARTY		Observations:		
9. Were the materials in good shape?	100		Indicators:		
Nasa maayos na kondisyon ba ang mga materyales?			no rust / no cracks and lamina		inations / no
			surface irregula	gularities or mill scale	
		7.4			a senat
10. More the type size and sweethers		بببين	Observations:		
10. Were the type, size and quantity of materials in accordance with the Program of Works?			If not in ac	cordance to Po	DW, Please
Ayon ba sa Program of Works ang uri, sukat at bilang ng	end at		Type	erate variations	And in contrast of the last of
materyales?		*	Type	Size	Qty
	The second		Liveral mailgos		
					85 CV
. Brode 2 dO			de que incien	041 1 10	
					a property of
11. Were the materials stored properly?	,		Indiant	- 0.000 00 601	La Val
Maayos ba ang pag-iimbak sa mga materyales?			Indicators:	datform ===1	
	terrent !	Isteron	☐ Placed on a p	nation of abo	ve ground
		SECTION	a a gods not pe	se dandër or îl	july to people
	-bered		Observations:	n - xixty g yelr	
Activity 3: Masonry					
1. Was the size of hollow blocks used in accordance with the			Program of Wo	rks:	4
			Actual:		Particular of the second
Program of Works and suket no hollow blocks used in accordance with the Program of Works and suket no hollow blocks.				rks:	4

2. Was the size of steel bars used in accordance with the Program of Works?  Ayon ba sa Program of Works and sukat ng steel bars?		Program of Works: Actual: Observations:			
3. Was the size of wires used in accordance with the Program of Works?  Ayon ba sa Program of Works ang sukat ng wires?		Program of Works: Actual: Observations:			
Activity 4: Carpentry					
1. Did the contractor buy the right number, size, and shape of materials as stated in the Program of Works?		If not in accordance to POW, Please enumerate variations below:			
Ayon ba sa Program of Works and bilang, sukat at hugis ng mga biniling materyales?		Type Size Qty			
Were the timber materials in good condition?  Ang mga kahoy ba ay nasa maayos na kondisyon?	*	Indicators:  □ no loose knots / no split / no worm hole / no decay / no warp / no ring separation			
Were the materials stored properly?     Maayos ba ang pagkaimbak ng mga materyales?	ď				
Activity 5: Painting					
Was the paint of good quality?     Maayos ba ang kalidad ng pintura?		Indicators:  □ no excessive setting / no curdling / no caking / no gelling or thickening / no color separation / no lumps and skins			
		Observations:			
2. Did the paint brush easily?  Madali bang lumapat ang pintura?		Indicators:  □ with good levelling properties / no rupning or sagging when applied to smooth vertical surface			
		Observations:			

# POST-CONSTRUCTION STAGE

Monitoring Points	Yes	No .	Details	
Process		8		
Was the schedule announced prior to construction?  Ipinaalam ba ang schedule bago magsimula ang konstruksyon?			When:	
Was construction completed within schedule? Natapos ba ang konstruksyon ayon sa schedule?			Start: End:	
Was a Joint Final Inspection conducted?  Nagsagawa ba ng joint Final Inspection?			When: Inspection Team members:  □ DPWH □ DepED □ Barangay □ PTCA □ CSO	
Were defective works rectified within 15 days?			Defects rectified:	

Monitoring Points	(-)	(+)	Comments / Observations
Structure	8 3 8		
Concreting Wall & Column Footings Tie Beams/Beams Floor Slab Columns			
Roofing & Accessories Trusses/Rafters Purlins Corrugated GI Sheet Teckscrew			
Doors and Windows Panel Doors Flush Doors Steel Doors Steel Casement Windows Jalousie Windows			
Plumbing Works Pipes Fittings Fixtures			
Painting Works Roofings Interior & Exterior Walls Ceiling Doors & Windows			
Electrical Fixtures Rough-ins Wires Fixtures Bulbs/Fluorescents			

# CONDUCIVENESS TO BEARNING

Monitoring Points	YES	NO	Comments / Observations
Indicators	1		
Ventilation: Are the classrooms well-ventilated? Maaliwalas ba ang loob ng mga silidaralan?			
Lighting: Are the classrooms sufficiently lighted? Sapat ba ang liwanag sa loob ng mga silid-aralan?			
Space: Are the classrooms spacious enough for the students? Sapat ba ang lawak ng mga silidaralan para sa mga estudyante?			
Sanitation: Was the school building site sanitary? Malinis be ang pinagtayuan ng mga silid-aralan?			What are the threats?  How are they addressed?

The Annual Control of the Control of			
banta sa kalusugan?			2 :
Safety: Does the school building have safety features? Mayroon Bang safety features ang silid-aralan?  Were there safety risks in the construction of the SBP? Nagkaroon ba ng mga banta sa kaligtasan noong itinatayo ang mga silid-aralan?		□ Emergency exit □ Security Grills □ Ramp	
Others: What other aspects of the school building is either commendable or should still be improved? Ano pang aspeto ng silid-aralan ang kapuri-puri o kaya naman ay dapat pa ipagouti?	Still needs im		

### RESPONSIVENESS TO SCHOOL NEED

Monitoring Points	YES	NO	Comments / Observations			
Is the school under the Red and Black Category (Fed – Equal to or more than 56 students per classroom; Black – No classroom available)?  Nasa Red and Black Category ba ang eskwelahan, na nangangahulugang nasa 56 o higit pa ang estudyante kada silid-aralan o kaya ay walang silid-aralan sa eskwelahan?			Number of Classrooms: Number of Makeshift Classrooms: Number of Condemnable Classrooms: Number of Buildings: Number of Condemnable Buildings:			
Is the design of the classroom appropriate for the school environment?  Naangkop ba ang disenyo ng silidaralan sa kapaligiran ng eskwelahan?						
Is the design of the classroom appropriate for the community's culture?  Naangkop ba ang disenyo ng silidaralan sa kultura ng komunidad?						

# IMMEDIATE CONCERNS OF THE SCHOOL

Others:

What are the school's immediate concerns?

Ano pa ang ibang mahahalagang pangangailangan ng eskwelahan?